



SOVRINTENDENZA
TAL-PATRIMONJU KULTURALI
SUPERINTENDENCE OF CULTURAL HERITAGE

National Inventory of the Cultural Property of the Maltese Islands

NICPMI Inv. No. 1459

Date of Publication 28 June 2013

Property Name	Main Gate – Mdina		
Address	Mdina		
Town Name	Mdina	Toponym	-
Property Owner	Government	Local Council	Mdina
Guardianship Deed	-		
	Managing Body	Mdina Local Council	

Period	Modern (18th Century)		
Phase	Early Modern: Knights of St John (18th Century)		
Cultural Heritage Type & Value	Historical Architectural	Cultural Heritage Property Value Assessment	Outstanding
Property Function	Fortification	Conservation Area	UCA

Outline Description	Gateway
Property Description	<p>The Main Gate into Mdina is a large Baroque portal with superstructure which served as a corpo di guardia. The gate was built by the French Military engineer Charles Francois de Mondion and is elaborately decorated with rusticated double pilasters, trophies-of-arms and inscriptions. It was also served by a wooden drawbridge of the counterweight type which rotated on itself and was known locally as à la Vauban (i.e., in the French style). This type of drawbridge consisted of a simple, counterbalanced platform, pivoted roughly in the middle, which when pulled up swung downwards inside the gateway's passage and into an underground chamber, the so-called 'cantina del ponte levatoio'. The underground chamber still exists as does the sally-port which opened beneath the gateway. The gate was approached via an arched bridge decorated with lion effigies holding escutcheons with the coat of arms of Grand Master Vilhena. The original medieval gateway, which Mondion's gate replaced, is situated to the right of the entrance, and is walled up.</p>

Scheduled by MEPA	Yes	Degree of Protection	Grade 1	G.N. No.	348	G.N. Date	2001
--------------------------	-----	-----------------------------	---------	-----------------	-----	------------------	------

Recommended Bibliography	<p>S.C. Spiteri, Fortresses of the Knights (Malta,2001), 229-36</p> <p>Q. Hughes & K. Thake, Malta, The Baroque Island (Malta, 2003), 156</p>
---------------------------------	---


Coordinates : Easting

46210

71527

Northing : Coordinates

Property Plan



Property Images

